

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce 96.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 9 E. W.	C-2
2. PROPERTY CONTROLLING IN SECTION--	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION--	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT. _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on 11/9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:
 C-2 Corner bet. Secs. 5-6, set in 1850 by Harvey Hellen, D. S.
 Bore: 16" 116° 21 Lks
 Cedar 13" 325° 48 Lks

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
 Corner re-established by proportionate measure bet. Sec. Corners 1/2 mile to North and 1/2 mile to South. No evidence of original Corner. Position checks with top of ridge to North.
 Corner 115' at foot of ridge and on an N-S fence line.
 Found a post for erroneous corner location; 236' South of the true location, set by unknown persons.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 Placed 1" pipe with 4" aluminum cap at corner.
 New bearings:
 16" Bore 126° 38.2'
 5" Bore 15° 14.3'

SIGNED BY Billy D. Buckler DATE 11/27/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 5227 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____ (SEAL)