

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970.**  
Luce Co. Two Corners

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. <u>46</u> N. <u>9</u> R. <u>9</u> <u>W.</u>	C-3 C-4
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11/9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

C-3 Sec. Cor. 5-6-7-8, set by Harvey Mellen, D.S. in 1850.  
Bearings were:

Cedar 14" S60°W 31 Links  
Cedar 12" N42°E 20 Links

C-4  $\frac{1}{4}$  Corner bet. Secs: 7-8, set by Harvey Mellen, D.S. in 1950.

Bearings were:

Cedar 6" S66°E 14 Links  
W. Pine 14" N60°W 6 Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

C-3 Corner replaced in an old winter road, from Cedar B.T.s': the NE Cedar is down with face and scribe marks in good condition. Found a Cedar stake point, 2 feet deep in wet muck. Believe this may possibly have been the original stake.

C-4 Corner replaced from W. Pine B.T. in excellent condition. Stump cut above lower face. Found remains of Cedar B.T. badly rotted.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
Placed 1" pipe with 4" aluminium cap at both corners.

C-3 new Bearings:  
5" Cedar S24°E 23.0' and 5" Cedar N76°W 16.5'

C-4 new Bearings:  
6" Cedar S17°E 12.1' and 9" Cedar N34°W 7.0'  
Corner lies 20' East of old winter road.

SIGNED BY Billy D. Buckler DATE 11/27/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8807 (SEAL)

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_