

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
 Luce Co. Iron Co.

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 2 E.	L-7 K-6 I-6
2. PROPERTY CONTROLLING IN SECTION	T. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 8/31 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-7 1/4 Corner bet. Secs., 13-24, set by Harvey Kellen, D.S. in 1850.
Bearings were: Spruce 4" N65°E 15 Links and Spruce 7" S55°W 4 Links
- K-6 1/4 Corner bet. Secs., 13-14, set by H. Kellen, D.S. in 1850.
Bearings were: Spruce 8" N29°E 1.56 chs. and Tamarack 8" S2°W 35 Links
- I-6 1/4 Corner bet. Secs., 14-15, set by H. Kellen, D.S. in 1850.
Bearings were: Y. Pine 8" N41°E 17 Links and Spruce 7" S39°W 11 Links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-7 Corner re-established midway and on line bet. two Sec. Cors. No evidence of original corner.
- K-6 Corner re-established midway and on line bet. two Sec. Cors. No evidence of original corner.
- I-6 Corner re-established, on top of an E-W ridge, as record indicates. Distances check well. Believe pine B.T. was removed by logging road construction. Corner lies 10' North of log road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- L-7 New Bearings: 10" Tamarack N32°W 28.0' and 10" B. Spruce N10°E 19.8'
- K-6 New Bearings: 8" Jack Pine S16°E 32.3' and 8" Jack Pine S58°W 40.5'
- I-6 New Bearings: 12" Hemlock S47°E 2.5' and 20" W. Pine N18°W 53.3'

SIGNED BY Billy D. Buckler DATE 11/27/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 3887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY _____ DATE _____

APPROVED AND SIGNED BY _____ MICHIGAN REGISTERED LAND SURVEYOR _____ DATE _____ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____