

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

Luc Co.

Two Corners.

FOR CORNERS OF --	LOCATED IN --	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> N. <u>3</u> R. <u>9</u> E. <u>W.</u>	J-3 G-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on J-3, 7/3-0-6, 7/5 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- J-3 Original  $\frac{1}{4}$  Cor. bet. Secs. 2-11, set by Harvey Mellen, D.S. in July 1850. Procedure was: A 3-mile random, beginning at Sec. Cor. 3-4-9-10, was run East to Twp. Line and corrected back, on a straight line. Distance was divided equally. Bearings were: Spruce 4" S61°E 11 Links and Spruce 5" N49°W 3 Links.
- G-6 Original  $\frac{1}{4}$  Cor. bet. Secs. 15-16 set by Harvey Mellen, D.S. in July 1850. Bearings were:  
 Cedar 14" N54°E 24 Links  
 Spruce 8" S67°W 5 Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- J-3 Found no original evidence of this corner. We did find an old blazed Cedar, intended to be on the N-S  $\frac{1}{4}$  line, Sec. 11. Mr. Glenn Hunter, Newberry, a landowner, remembers this corner to have been by the old road. Corner re-established from Swamp edges, a few old blazes to West and South of Corner.
- G-6 Replaced Cor. from one Cedar Stump, a probable witness, in poor condition. Position checks well with Sec. Cor.  $\frac{1}{2}$  mile South and  $\frac{1}{4}$  Cor. one mile North. Found a squared Hemlock 10" NE of corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Placed 1" pipe with 4" aluminium cap at both corners.
- J-3 New Bearings:  
 18" W. Pine N29°E 26.4'  
 9" B. Spruce S37°W 13.8'  
 Corner lies on North side of an old woods road.
- G-6 New Bearings:  
 26" W. Pine S40°E 20.9'  
 24" W. Pine N87°W 36.1'  
 Corner lies 20' North of a road and 40' East of a road.

SIGNED BY Billy D. Buckler DATE 7/19/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 3887 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_