

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

Luce Co.

Two Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> N. <u>3.</u> R. <u>9</u> W.	M-7 K-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. _____ S. _____ R. _____ E. _____ W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/27 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- M-7 Sec. Cor. 13-24, on East Two Line set originally, June 28th, 1840.
 Bearings were:
 Spruce 6" S73°W 6 lks and Y. Pine 20" N14°W 28 lks and
 Spr. Pine 10" S50°E 24 lks.
- K-5 Sec. Cor. 11-12-13-14, set by Farvey Mellen, D.S. in 1850.
 Bearings were:
 Sp. Pine 6" N29°E 12 lks and Sp. Pine 8" S36°E 81 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- M-7 Found no positive evidence of original corner. Found some blazes and scars on a down Jack Pine near corner but could not define position. Corner placed at record distance South of a good corner, 1/2 mile North. Swamp edges to East and South check well. Corner lies on a pine ridge.
- K-5 Corner placed by single proportionate measure bet. corners to East and West. No evidence fo original.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at both corners.
- M-7 New Bearings:
 12" Jack Pine S28°W 10.5'
 12" Jack Pine N89°E 29.0'
- K-5 New Bearings:
 7" Black Spruce S86°E 109.2'

SIGNED BY Billy D. Buckler DATE 8/2/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8867 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____