

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
 Luce Co. Two Corners

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. R. 9 E.	I-5 C-7
2. PROPERTY CONTROLLING IN SECTION	T. _____ N. S. R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION	T. _____ N. S. R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 7/27 8/4 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

- I-5 Corner placed by Harvey Mellen, D.S. in 1850.  
Bearings were:  
Spruce 5" N30°E 21 Links and W. Birch 7" S55°W 19 Links
- C-7 Sec. Cor. 17-18-19-20., placed by Harvey Mellen, D.S. , 1850.  
Bearings were:  
Cedar 7" N53°W 34 Links and Cedar 7" S35°E 9 Links

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- I-5 Corner re-established by Single Proportionate Measure bet. corners to East and West. Found an old line of blazes to North of Corner. Distance South (50 LKS) to swamp agrees.
- C-7 Corner placed at an old Cedar tree with blazes facing corner. Found blazes to N-E-W. No original evidence.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**  
 Placed 1" pipe with 4" aluminium cap at both corners.

- I-5 New Bearings: 36" W. Pine S61°W 37.3'  
15" W. Pine S66°E 42.7'
- C-7 New Bearings: 7" Cedar S5°W 7.1'  
7" Cedar N68°E 20.4'

SIGNED BY Billy D. Buckler DATE 8/16/72

SURVEYOR'S MICHIGAN REGISTRATION NO. 8857 (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_ MICHIGAN REGISTERED LAND SURVEYOR DATE \_\_\_\_\_ (SEAL)