

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**  
Luce Co. 2 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> <sup>N.</sup> <del>X.</del> , R. <u>9</u> <sup>K.</sup> <del>W.</del>	A-8    B-9
2. PROPERTY CONTROLLING IN SECTION _____	T. _____, S., R. _____, E., W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____, S., R. _____, E., W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER


I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 2-10, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

- A. Description of original monument and accessories and/or subsequent restoration:
- A-8 Quarter Corner on West side of Section 19, set by Wm. Austin Burt, D.S. in 1841. Bearings were: Beech 10", S60°W, 17 lks. and Hemlock 14", N67°E, 34 lks.
  - B-9 Quarter Corner bet. Sec's. 19-30, set by Harvey Kellen D.S. in 1850. Bearings were: Cedar 12", N22°E, 17 lks. and Cedar 14", S16°W, 13 lks.

- B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:
- A-8 Re-witnessed corner as set by unknown Surveyor. Found 2" Iron Pipe at corner.
  - B-9 Restored corner by Single Prop. Measure between section corners and in line with old fence to South.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- A-8 Placed 1" pipe with 4" aluminium cap at corner. New Bearings: 6" H. Maple, N40°E, 12.8' and 6" R. Maple, S42°W, 14.5'.
  - B-9 Buried 1" x 40" pipe, 19.6' South of road center line. New Bearings: 12" W. Pine, S31°W, 34.7'.

SIGNED BY Billy D. Buckler DATE 2-9-79  
 SURVEYOR'S MICHIGAN REGISTRATION NO. 8887



FOR STATE AND UNITED STATES AGENCIES:  
 SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
 APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)