

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970
Luce Co. 3 Corners

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	4-Sec. 20
2. PROPERTY CONTROLLING IN SECTION <u>20</u>	, T. <u>46</u> N. S., R. <u>9</u> E. W.	3-Sec. 20 8-Sec. 20
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____	, RECORDED PLAT _____	_____
5. PRIVATE CLAIMS _____	_____	_____

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on 1-31-, 1975, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 4-Sec. 20 Northwest 1/16 Corner of Section 20.
- 3-Sec. 20 North 1/16 Corner of Section 20. *set 19-20*
- 8-Sec. 20 West 1/16 Corner of Section 20.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:


- 4-Sec. 20 Placed corner at center of the Northwest quarter section.
- 3-Sec. 20 Placed corner midway bet. $\frac{1}{4}$ corner to North and Center Corner to South.
- 8-Sec. 20 Placed corner midway bet. $\frac{1}{4}$ corner to West and Center Corner to East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Placed 1" pipe with 4" aluminium cap at all corners.
- 4-Sec. 20 No witnesses available.
- 3-Sec. 20 Bearings: 6" Cedar, N53°E, 68.4' and 6" Cedar, N34°W, 25.7'.
- 8-Sec. 20 Bearings: 8" Balsam, N34°W, 36.9'.

SIGNED BY Billy D. Buckler

DATE 2-9-79



SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. _____