

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____ Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T46N R 9W C-11
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

LUCE COUNTY
REGISTER OF DEEDS
Recorded

02-29-1996 15:16:53

Liber 2 Page 644

Kathy S. Mahar, Register
REGISTER OF DEEDS

Kathy S. Mahar

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/11, 1995, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
C-11 Corner Common to Sections 29, 30, 31, & 32, Town 46 North, Range 9 West
1850 - Original ties to set post: Tamarack 12, S61°W 05 links - Cedar 9, N20°E 06 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Luce County Remonumentation Program.
Found no evidence of this corner or its accessories. The east-west position of corner was determined by proportionate distance with original GLO notes between recovered 1/4 corners B-11 to the west and D-11 to the east. The north-south position was established 33 feet north of the remains of an east-west right of way fence in Section 32, on the south side of County Road 466. This position places 1/4 corner D-11 within 0.8 feet of a split between Section corners east and west. Corner falls in the approximate centerline of County Road 466.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rebar with a 3" aluminum Luce County Remonumentation cap in the approximate centerline of east-west gravel road (County Road 466). Witnesses:
14" Tamarack, S34°W 50.38' (Nail/tag P.S. 33142 in side)
9" Cedar, S01°W 39.29' (Nail/tag P.S. 33142 in side)
6" Cedar, S24°E 52.32' (Nail/tag P.S. 33142 in side)
Power Pole, N44°E 57.75' (Nail/tag P.S. 33142 in side)
1/2" Iron with cap #33142, NORTH 50.00'

Note: Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-29-95

