

LUCE COUNTY REMONUMENTATION CORNER

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T45N R 9W T46N R 9W	C-1 Same C-13 Corner
2. Property Controlling in Section	S ___ T ___ R ___	___
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	___

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 91 478
Keith R. Waters
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters in a field survey on September, 1993 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

C-1 Corner Common to Secs. 5 & 6, T45N, R9W, and Secs. 31 & 32, T46N, R9W

- Original ties to post:
- Cedar 8, N39°E 36 links
- Cedar 16, N49°W 16 links
- B. Ash 12, S45°W 24 links
- Fir 18, S60°E 63 links



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

C-1
This corner is being perpetuated as part of the Luce County Remonumentation Program. Found a spike with i.d. tag Eino Sainio, L.S. 7873, inside a 1 3/4" iron pipe next to a squared cedar post on the north edge of a swampy, grown over 2-track road. In talking with Eino he indicated that he established corner position using some found original and subsequent County Surveyor evidence. Distance to Section corner 1 mile south is within 4.5 feet of original G.L.O. distance. Accepted corner position as found and replaced spike with a 1/2" iron and 3 1/4" aluminum Luce County cap.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-1
Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap inside a 1 3/4" pipe on the north edge of east-west trail. Witnesses:

- 3" Aspen, N14°W 21.95'
- 6" Aspen, N56°E 34.25'
- 7" Balsam Fir, S04°E 24.10'
- 5" Balsam Fir, S18°W 22.30'

Note: Distances are to a nail and tag in the side of tree. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142