

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T46N R 9W	D-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 2 Page 657*  
07-29-1996 15:22:24  
*Kathy S. Mahar*  
Kathy S. Mahar, Register  
REGISTER OF DEEDS  
Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 08/31, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:


NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	10		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9			●									
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
D-9 1/4 Corner Common to Sections 20 & 29, Town 46 North, Range 9 West  
1850 - Original ties to set post: Maple 10, S74°E 18 links - Hemlock 14, N69°W 27 links.  
1975 - Billy D. Buckler, R.L.S. 8887, Luce County recorded corners, page 270. Restored 1/4 corner between two Section corners. Corner lies 6.15' west of a wood post. Witnesses: 8" Spruce, S67°W 12.0' - 8" Red Pine, S68°E 16.0'. Corner lies 6.15' west and 60.85' south of the wood post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
This corner is being re-established as part of the Luce County Remonumentation Program. Found a 1" pipe with a DNR cap as called for in 1975 LCRC. Also found the red pine bearing tree, the spruce is dead and has fallen down. It appears that the 1" pipe was mistakenly placed on the line between the Section corner E-9 and a witness corner to the Section corner C-9, which was 13.0 feet south of the Section corner location. Re-established 1/4 corner by single proportionate measurement on line between Section corner E-9 and the correct position of Section corner C-9. Corner falls 7.3 feet north of the found 1" pipe, approximately 26 feet south of the centerline of east-west gravel road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
Corner is a 1/2" rebar with a 3" aluminum Luce County Remonumentation cap, approximately 26 feet south of the centerline of east-west gravel road (County Road 462), 65 feet east of the east end of asphalt pavement on said road. Witnesses:  
14" Red Pine, S48°E 20.76'  
10" Balsam Fir, S04°W 35.42'  
7" Spruce, S43°W 34.63'  
9" Red Maple, S69°W 18.05'  
1" Iron pipe with DNR cap, SOUTH 7.3'  
Note: Distances are to a nail/tag P.S. 33142 in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-29-95