

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R9W	D-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LUCE COUNTY
REGISTER OF DEEDS
Recorded
Kathy S. Mahar
02-29-1995 15:17:04
Liber 2 Page 645
Kathy S. Mahar, Register
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/11, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11			●										
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:
D-11 1/4 Corner Common to Sections 29 & 32, Town 46 North, Range 9 West
1850 - Original ties to set post: Cedar 10, N17.5°E 21 links - Cedar 5, S40°W 16 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.
Found a 1 1/2" x 12" iron pipe at the surface of east-west gravel road, on the extension of a fence line to the south. Removed pipe and found another 1 1/2" pipe and remains of a wood post 16" below road surface. Placed a 1/2" rebar with a 3" aluminum Luce County Remonumentation cap inside found pipe, 6" below road surface. Corner is 2640.47 feet from Section corner to the west, 2638.84 feet from Section corner to the east, and is 1.3 feet south of a straight line between said Section corners. Corner is also 33 feet north of an east-west right of way fence on the south side of County Road 466.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rebar with a 3" aluminum Luce County Remonumentation cap placed inside a found 1 1/2" pipe. Corner is approximately 4 feet south of the centerline of east-west gravel road (County Road 466), on the extension of a fence line to the south. Witnesses:
11" Tamarack, S59°E 178.59'
7" White Birch, N42°E 131.75'
4" Balsam Fir, N61°E 123.18'
1/2" Iron with cap #33142, NORTH 50.00'

Note: Distances to trees are to a nail/tag P.S. 33142 in the side. Trees are blazed and painted.
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-29-95