

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____ (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>9W</u>	<u>E-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LUCE COUNTY
REGISTER OF DEEDS
Recorded
02-29-1996 15:17:17
Liber 2 Page 646
Kathy S. Mahar, Register
REGISTER OF DEEDS
Kathy S. Mahar
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/07, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

E-11 Corner Common to Sections 28, 29, 32, & 33, Town 46 North, Range 9 West
1850 - Original ties to set post: Cedar 8, N25°W 17 links - Cedar 6, S38°E 27 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of Luce County Remonumentation Program.
Found no evidence of this corner or its accessories. Re-established corner 33 feet north of a corner fence post on the south side of County Road 466. The distance east to recovered Section corner G-11 is within 4 feet of the original GLO distance. This position also puts the recovered 1/4 corner D-11 within 0.8 feet of a split between Section corners east and west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rebar with a plastic cap #33142 approximately 3 feet south of the centerline of east-west gravel road (County Road 466), on top of a 24" north-south CMP under said road, 33 feet west of centerline of drives north and south. Witnesses:
5" Cedar, N46°E 118.32' (Blazed and painted, nail/tag P.S. 33142 in side)
North end of 24" CMP, NORTH 17.35'
South end of 24" CMP, SOUTH 12.70'
Center of top of 3' high, 3" diameter steel gate post on the west side of gravel drive to the south, S42°E 41.96'

Note: Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-29-95