

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____
(County)

Located In:	Corner Code #
T46N R9W	F-11
T R	
T R	
T R	
S T R	
S T R	
S T R	
S T R	

1. Public Land Survey

2. Property Controlling in Section

3. Miscellaneous Property in Sec.

LUCE COUNTY
REGISTER OF DEEDS
Recorded
Kathy S. Mahar
02-29-1996 15:17:34
Liber 2 Page 647
Kathy S. Mahar, Register
REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/07, 1995 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:
F-11 1/4 Corner Common to Sections 28 & 33, Town 46 North, Range 9 West
1850 - Original ties to set post: Cedar 10, N53°W 08 links - Spruce 8, S24°E 33 links.

Found no evidence of subsequent restoration of this corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of Luce County Remonumentation Program.
Found no evidence of this corner or its accessories. Re-established corner mid-way on line between Section corners 2650.86 feet east and 2650.86 feet west. Original GLO distances were 2648.9 feet east and 2648.9 feet west.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rebar with a plastic cap #33142 in the approximate centerline of east-west gravel road (County Road 466).

Witnesses:

- 6" Aspen, S20°E 82.16'
- 4" Aspen, N25°E 47.09'
- 7" Aspen, N10°E 57.64'
- 16" Aspen, N37°W 71.32'

Note: Distances are to a nail/tag P.S. 33142 in the side. Trees are blazed and painted.
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-29-95