

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>46N</u> R <u>9W</u>	<u>13</u>	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 29 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3									●				
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(I3) Corner common to Sections 2-3-10-11. 1850 - Established by Harvey Mellen, Deputy Surveyor: Corrected West between Sections 2 and 11 ... 80.34 Set post corner of Sections 2-3-10-11. Tamarac 8 N73E 12, Tamarac 7 S67W 9. The 1850 record also gives 80.34 as the length of the line between Sections 3 and 10. 1972 - Reestablished by Billy D. Buckler, RLS: Found no evidence of original corner, so reestablished corner on line between corners 1/2 mile East and one mile West. Set 1" pipe with 4" aluminum cap. 8" Cedar N9W 28.0', 8" Cedar S2W 16.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I3) Found the 1972 monument in good condition and at record bearing and distance from the 1972 witnesses, both in good condition with blazes still open. A close examination of the field notes of the 1972 survey and a comparison of those notes to my measurements to monuments at G3 and J3 show that while Mr. Buckler installed this monument substantially at the position he calculated, his figuring of the proportionate position was not strictly correct. As a result, he monumented I3 about 32 feet west of the single proportionate position. My measure between G3 and J3 is 8043.52' and the 1972 monument at I3 was found 2712.89' West of J3. Local land owners have used this 1972 position and have accepted it as the Section corner. Consequently, I decided to accept it as marking the position of the reestablished Section corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 8" Cedar S06W 16.65' old blazes *
 10" Cedar N06W 28.65' do *
 8" W. Birch S36E 6.65' mrkd "S11 NBT"
 7" Cedar S40W 16.45' "S10 NBT"
 Bearings are magnetic. Distances are to nail with tag. * denotes 1972 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/22/05