

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>9W</u>	<u>J3</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Mar 29 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3										●			
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(J3) Quarter corner common to Sections 2-11. 1850 - Established by Harvey Mellen, Deputy Surveyor: Corrected West between Sections 2 & 11 ... 40.17 Set post Qr. Section corner. Spruce 4 S61E 11, Spruce 5 N49W 3. ... 80.34 Set post corner of Sections 2-3-10-11. 1972 - Remonumented by Billy D. Buckler RLS using local evidence and testimony of a landowner. Set 1" pipe with 4" aluminum cap. 18" W.Pine N29E 26.4', 9" B.Spruce S37W 13.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(J3) Found the 1972 monument in good condition and at record bearing and distance from the 1972 witness trees. The W.Pine NE is in good condition with an open blaze. The B.Spruce SW is now a rotting stump. Though the position of this monument is not strictly in conformance with the distances to nearby corners as they are shown in the original notes, I accept the monument as the best available evidence of the position of the original corner. From J3, I measure 7853.90' East to M3 (7953.7' GL0) and 8044.55' West to G3 (7953.7' GL0), J3 being 35.9' South of a straight line between them.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J3) Found 1" ID I.pipe with 4" alum. MDNR cap. Set measuring nails in:
 18" W.Pine N35E 26.8' open blaze *
 6" Maple S01W 20.35' mrkd "1/4S NBT"
 8" B.Spruce N64W 5.7' do
 4" B.Spruce S22E 10.4' do
 Bearings are magnetic. Distances are to nail with tag. * denotes 1972 NBT.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/22/05