

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce

(County)

Located In:

Corner Code #

1. Public Land Survey

T 46N R 9W K2
 T R _____
 T R _____
 T R _____
 T R _____

2. Property Controlling in Section

S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____
 S _____ T _____ R _____

3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 04 2005

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (K2) Quarter corner common to Sections 1-2. 1850 - Established by Harvey Mellen, Deputy Surveyor: Corrected north between Sections 1 and 2 ...40.02 Set Qr. Sect. post. Spruce 6 S83W 18 links, Tamarac 5 S46E 33 links. ... 80.02 Section corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(K2) The original post and accessories were not recovered. Found no evidence of subsequent perpetuation. Reestablished the corner by single proportionate measurement to the original record between monumented corners K1 and K3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(K2) Set 1"IDx36" I.pipe with 4" alum.
 MDNR cap. Set measuring nails in:
 8" Maple S22W 27.15' mrkd "1/4S NBT"
 18" R.Pine S76W 13.2' do
 12" Spruce N13W 5.8' do
 8" Tamarack N46E 15.65' do
 Bearings are magnetic. Distances are to nail with tag. The center of the Charcoal Grade is approx. 32' South.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 6/22/05