

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce	Located In:	Corner Code #	
(County)			
1. Public Land Survey	T <u>46N</u> R <u>9W</u>	<u>K5</u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
	T <u>    </u> R <u>    </u>	<u>    </u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 24 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5											●		
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (K5) Corner common to Sections 11-12-13-14. 1850 - Established by Harvey Mellen, Deputy Surveyor: N89-59'W corrected between Sections 12 & 13 ... 80.26 Set post corner of Sections 11-12-13-14. Sp. Pine 6 N29E 12, Sp. Pine 8 S36E 81. 1972 - Reestablished by Billy D. Buckler RLS: Corner placed by single proportionate measure bet. corners to East and West. No evidence of original. Set 1" pipe with 4" aluminum cap. 7" B.Spruce S86E 109.2'

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(K5) Found the 1972 monument in good condition. The 1972 NBT was not recovered. The monument was found in the 1972 position as evidenced by its proper relationship to corners I5 and J5 to the west. A close examination of the notes of the 1972 survey revealed that Mr. Buckler did not recover corner L5 or M5, as implied by a casual reading of his record, but rather used the location of monumented corner M6 and its Easting to develop a basis for his proportionate position. Though I did not reestablish corners L5 or M5 in my survey, I calculated a proportionate position for M5 between M3 and M6 and used it to verify the validity of Mr. Buckler's proportionate solution for K5. I found Mr. Buckler's K5 monument to 6 feet East and 17 feet North of the proportionate position as I calculated it. Those differences are well within the range of differences I observed between my own measure and the record of the 1972 survey in this part of the township. In consequence, I accept the 1972 monument as a reasonable reestablishment of the position of the original corner.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(K5) Found 1" ID I. pipe with 4" alum. MDNR cap. Set measuring nails in:  
 4" J.Pine S23E 14.95' mrkd "S13 NBT"  
 7" J.Pine S57E 44.8' do  
 7" J.Pine S72E 55.1' do  
 4" Tamarack N50E 53.95' mrkd "S12 NBT"  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/22/05