

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce  
 (County)

Located In: Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>9W</u>	<u>L3</u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
	T <u>    </u> R <u>    </u>	<u>    </u>
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>
	S <u>    </u> T <u>    </u> R <u>    </u>	<u>    </u>

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 24 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:  
 (L3) Quarter corner common to Sections 1-12. 1850 - Established by Harvey Mellen, Deputy Surveyor: Corrected West between 1 & 12 ... 40.17 Set post Qr. Section corner. Tamarac 7 S46E 37 links, Tamarac 5 N25W 15 links. ... 80.34 Set post corner of Sections 1-2-11-12.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(L3) The original post and accessories were not recovered. Found no evidence of subsequent perpetuation. Reestablished the corner by single proportionate measurement to the original record between monumented Section corners K3 and M3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(L3) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
 10" Spruce S54E 17.4' mrkd "1/4S NBT"  
 8" Spruce S30W 24.4' do  
 8" Spruce N83W 8.1' do  
 6" twin Spruce N17E 19.55' do  
 Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/22/05