

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luçe	Located In:	Corner Code #
(County)		
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S <u>11</u> T <u>46N</u> R <u>9W</u>	<u>2</u>
	S <u>11</u> T <u>46N</u> R <u>9W</u>	<u>5</u>
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Mar 23 2005

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:  
 (2-Sec. 11) East 1/16 corner between Sections 2 and 11. Not established in the original survey.  
 (5-Sec. 11) North 1/16 corner, Sec. 11. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (2-Sec. 11) Established the corner on the section line and midway between Section corner 1309.19' East and Quarter corner 1309.19' West.  
 (5-Sec. 11) Established the corner midway and on a straight line between Quarter corner 1302.15' North and Center of Section 1302.15' South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 3" B.Spruce N40W 6.1' mrkd "E1/16 BT" 4" Tamarack N50E 12.15' do 4" Tamarack S32W 34.7' do 5" Tamarack S04W 28.0' do Bearings are magnetic. Distances are to nail with tag.	(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in: 4" Balsam S79W 15.75' mrkd "N1/16 BT" 12" Spruce N50W 30.9' do 5" Balsam S24E 26.55' do 5" Balsam S24W 21.5' do Bearings are magnetic. Distances are to nail with tag.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 6/22/05