

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

**LUCE COUNTY**

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>46</u> N. S., R. <u>10</u> E. W.	<u>I-11</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler, R.L.S., do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 7, 1976, 19\_\_\_\_, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:  
**I-11; Section Corner 26-27-34-35, set by George E. Cannon, D.S., July 28, 1853.**  
 Bearings were;  
 Hemlock 18", N 80° W, 59 Links. and Hemlock 16", S 40° E, 19 Links.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:  
**I-11;**  
 Monumented this corner at a 2" Iron Pipe, buried 16" deep, in ground. Corner found by E.A. Sainie, RLS, while conducting a survey in this area. There is another Point (3/4" Iron Pipe) N 75° E, 40.5', which has been used for conveyancing of land, during the last three years.; however this point does not fit evidence in every direction, as the 2" Pipe does.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
**I-11;**  
 Placed 1" pipe with 4" Aluminum Cap beside the buried Pipe.

Marked New Bearings;  
 14" Soft Maple, S 66° W, 27.0'  
 14" Soft Maple, S 30° E, 58.0'  
 SE Corner of Building, N 23° W, 76.9'

SIGNED BY Billy D. Buckler, R.L.S. DATE 8/20/76.

SURVEYOR'S MICHIGAN REGISTRATION NO. 8887.

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

