

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR 10 W

Luce COUNTY

DESCRIPTION OF CORNER Section corner common to Sec.'s 3-4-9-10  
DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap  
WITNESSES TO CORNER 7" Cedar N 86° E 33 links  
"S 3 NBT"  
8" Cedar S 48 E 34 links  
"S 10 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced section corner from two cedar B.T.s bearing N 35° W 48 links and S 35° E 22 links; both stumps down and in poor condition. Scribe marks "NBT" plain on NW stump. Found 1½" iron pipe 4 links west of corner.

Found while checking lines run by District Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckles DATE 11/8/57  
REGISTERED LAND SURVEYOR