

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~4647~~ NR 10&11 W

L u c e COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 6, 1, 36, 31

Also a township corner.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 12" Twin Elm (NBT) S 75° W 272 Links

10" Fence Post 71 1/2 Links

Corner lies 16 links south of road.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established 50 Links west and 50 Links south of old fence corner. Believe fence was built with an allowance for road. Other corners in the area support this. Position checks well for proportionate measure to east and west along township line.

Corner was placed and witnessed May 11, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

Billy D. Buckler

DATE 5/23/60