

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T ~~46-47~~ NR 10 W

Luce COUNTY

DESCRIPTION OF CORNER 1/4 corner between Sections 5 and 32

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 6" Hard Maple (1/4s NBT) S 25° E 73 Links

6" Hard Maple (1/4s NBT) S 30° W 72 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was re-established midway and on line between two section corners. Found no evidence of original corner. Corner lies on south edge of road.

Corner was placed and witnessed June 2, 1960 with Daniel Bonner, Ass't D.F.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 9/14/60