

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 46 N.R. 10 W.


Luce COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 10-11-14-15.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/16/63.

WITNESSES TO CORNER..... 10" Cedar Stump. (N.B.T.) N. 28° E., 19 Lks.



12" Cedar Stump. (N.B.T.) N. 54° W., 17 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established on an old line of N.-S. blazes and from an old stream bed 3.16 Chs. South. Possibility of another old vacated stream bed 10.20 Chs. South to fit record. Present stream follows an old Railroad Grade.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler* DATE 8-12-63  
REGISTERED LAND SURVEYOR