

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 N.R. 10 W.


Luce COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 11-14.

CORNER MONUMENT 1" Pipe with 4" Aluminum Cap.

DATE MONUMENT PLACED AND WITNESSED 5/16/63.

WITNESSES TO CORNER..... 7" W. Birch (1/4 S. N.B.T.) S. 10° W., 24 Lks.



7" Aspen (1/4 S. N.B.T.) S. 70° E., 21 Lks.

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was replaced from two probably B.T.s; a cedar stump bearing S. 20° E. 17 Lks. and a down cedar bearing N. 40° W. 19 Lks. Found old blazes facing East and West about 20 Lks. due West of Corner. Position checks well with Section Corners East and West.

SURVEYOR'S SEAL

SIGNED *Billy D. Buckler*
Billy D. Buckler DATE 8-12-63
REGISTERED LAND SURVEYOR