

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 & 47 N.R. 10 W


Line COUNTY

DESCRIPTION OF CORNER Section Corner common to Secs. 3-4, T46N10W & 33-34, R42E10W

CORNER MONUMENT 1/2" X 12" Reinforcing rod driven 4" below surface of Blacktop

DATE MONUMENT PLACED AND WITNESSED 4/7/64 with Forestry Aide Aubie and ... Birds

WITNESSES TO CORNER..... 5" Soft Maple (in clump) (NE) S02°E, 64 lns.



CIRCLE CORNER REGISTERED

5" Soft Maple (in clump) (NW) N04°E, 62 lns.

Corner lies 6 Links North of approximate center line of

AND
Blacktop Road Co. 407.

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This Corner was re-established by placing it on Line and midway between 1/4 Corners 1/2 mile to East and West.

SURVEYOR'S SEAL

SIGNED Frank J. Gray DATE 3/18/1964
REGISTERED LAND SURVEYOR