

# LAND CORNER RECORDATION CERTIFICATE

**FILING REQUIREMENT OF ACT 74, MICH. P.A.1970**  
Luce Co. Two Corners.

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 46 N. 8. R. 10 E. W.	G-5
2. PROPERTY CONTROLLING IN SECTION	7 T. 49 N. 8. R. 10 E. W.	16, Sec. 7
3. MISCELLANEOUS PROPERTY IN SECTION	, T. N. S. R. E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Billy D. Buckler do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 6/18 & 7/2 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

G-5 Section Cor. common to 9-10-15-16, set by Geo H. Cannon D.S. in 1853.  
Bearings were: Cedar 14, S64°E, 23½ lks. and Y. Birch 20, S82°W, 12 lks.

16, Sec. 7 East 1/16 cor. bet. Sections 7-18.  
(T47N R10W)

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

G-5 Replaced from possible B.T.'s, a cedar and Y. Birch in proper position.  
Found a line tree to North, 9.96 chains.

16, Sec. 7 Placed corner midway bet. ¼ corner to west and section corner to east.  
(T47N R10W)

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**


Placed 1" x 36" pipe with Dep't cap at all corners.

G-5 New bearings: 6" W. Birch, N85°W, 28.0'  
8" B. Spruce, S75°E, 10.5'

16, Sec. 7 Bearings: 10" S. Maple, S83°W, 21.8'  
10" S. Maple, S9°E, 16.2'  
(T47N R10W)

SIGNED BY Billy D. Buckler  
Billy D. Buckler

DATE 7/30/74



SURVEYOR'S MICHIGAN REGISTRATION NO. 8887

**FOR STATE AND UNITED STATES AGENCIES:**

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_