

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 10W	B3
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3	7	8	9	10	11	12							
4													
5	18	17	16	15	14	13							
6													
7	19	20	21	22	23	24							
8													
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 06/28/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B3) Quarter corner common to Sections 6 and 7. 1853 - Established by Geo.H.Cannon Deputy Surveyor in a correction survey of this township N89 deg. 27' E 39.16 chains from Section corner A3 and N89 deg. 26'W 40.34 chains from Section corner C3. Beech 12" N34W 12 links, Beech 8" S70E 21 links. 1974 - Billy D. Buckler RLS reestablished the corner by single proportionate measure between two Section corners. Set 1"IDx36" I.pipe with 4" alum. Department cap. 12" W.Pine N67E 8.9', 14" Spruce, West 6.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B3) The original post and accessories were not recovered. Found the 1974 monument in good condition and at record bearing and distance from the 1974 witnesses. The W.Pine NBT NE is in good condition. The Spruce NBT West has fallen. Found the easting of the corner to be in substantial accord with the record. The monument is approximately 24' north of a position which would make the deflection at this corner equal to the record GLO deflection between section corners. I note that land owners to the east in Section 7 have used the monument position to establish the section line in the course of making improvements to real property, and I accept the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B3) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 26" W.Pine N73E 9.05' mrkd "1/4 S" 1974 NBT
 16" triple W.Pine S78W 60.5' mrkd "1/4S NBT"
 10" Maple in clump N09W 23.1' do
 6" Balsam S11E 19.6' do
 Bearings are magnetic.



Signed by *Stephan J. Szyszkoski*
 Surveyor's Michigan License No. 33986

Date 06/14/2011

For the Michigan Department of Natural Resources, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971