

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 46N R 10W	A2 same
	T 46N R 11W	M2 corner
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/12/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(A2) Quarter corner common to Section 6 T46N-R10W and Section 1 T46N-R11W. 1841- Established by W.A.Burt Deputy Surveyor on the Range line 40.00 chains north of Section corner and 40.07 chains south of Township corner. Set post. Hemlock 36" N30E 27 links, Fir 12" N46W 26 links. 1974 - Billy D. Buckler RLS reestablished the corner by single proportionate measurement to the original record between Section corner 1/2 mile south and Township corner 1/2 mile north. Set 1"IDx36" I.pipe with 4" MDNR cap. 10" S.Maple S05E 11.7', 8" S.Maple N25W 0.8'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(A2) The original post and accessories were not recovered. Found the 1974 monument in good condition, substantially at the record position between Section and Township corners, and at record bearing and distance from the 1974 NBTs, both in good condition. Accepted the monument as a careful and faithful reestablishment of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(A2) Found 1"ID I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 12" Maple N19W 1.3' mrkd "1/4S" 1974 NBT
 16" Maple S01E 12.3' do do
 10" W.Pine S50E 19.95' mrkd "1/4S NBT"
 5" Maple S89W 19.2' do
 Bearings are magnetic.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division