

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>6</u> T <u>46N</u> R <u>10W</u>	<u>7</u>
	S <u>6</u> T <u>46N</u> R <u>10W</u>	<u>5</u>
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6												
3													
4	7												
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 7 06/29/2010 and 5 06/30/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(7-Sec. 6) North 1/16 corner between Sections 5 and 6. Not established in the original survey.

(5-Sec. 6) Center-North 1/16 corner, Section 6. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(7-Sec. 6) Established the corner on the Section line between Section corner 1303.29' north and Quarter corner 1334.76' south, being proportionate to the dimensions given on the GLO plat.

(5-Sec. 6) Established the corner on the N-S 1/4 line of Section 6 1326.14' north of the intersection of 1/4 lines of Section 6 and 1324.15' south of Quarter corner B1, the position being proportionate to the dimensions on the GLO plat.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(7) Set 5/8"x24" rebar with plastic MDNR cap. Set measuring nail with MDNR tag in the side of:
 11" R.Pine S46E 10.65' mrkd "N1/16 BT"
 14" W.Pine N03W 39.55' do
 12" Maple N77E 48.55' do
 10" Maple in clump S18E 33.6' do
 Bearings are magnetic.

(5) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
 8" W.Pine S86E 8.35' mrkd "N1/16 BT"
 6" Birch S09E 16.65' do
 12" Birch S66W 21.2' do
 10" W.Pine N14E 26.35' do
 Bearings are magnetic.

Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 10/26/2010



For the Michigan Department of Natural Resources and Environment, Forest Management Division