

MAY 28 1997

COMMISSION

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce  
(County)

Located In: Corner Code #

- |                                    |            |      |        |
|------------------------------------|------------|------|--------|
| 1. Public Land Survey              | T46N R 10W | F-1  | Same   |
|                                    | T47N R 10W | F-13 | Corner |
|                                    | T R        |      |        |
|                                    | T R        |      |        |
| 2. Property Controlling in Section | S T R      |      |        |
|                                    | S T R      |      |        |
| 3. Miscellaneous Property in Sec.  | S T R      |      |        |
|                                    | S T R      |      |        |

LUCE COUNTY  
REGISTER OF DEEDS

Recorded  
Liber 2 Page 708  
02-28-1997 08:54:02  
*Kathy S. Mahar*  
Kathy S. Mahar, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 12/10, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- F-1 (F-13) 1/4 Corner Common to Section 4, T46N, R10W & Section 33, T47N, R10W
- 1841 - Original ties to set post (John Burt): Tamarack 6, S56°E 22 links - Spruce 5, N64°W 40 links.
- 1957 - Billy D. Buckler, RLS 8887, page 163A of Luce County recorded corners. Replaced 1/4 corner from two original bearing trees in good condition. Placed 1" pipe with brass cap. Witnesses: 10" White Pine, S55°E 54 links - 7" White Pine, S57°W 21 links.
- 1996 - William L. Karr, P.S. 27450, Certificate of Survey. Found DNR brass capped pipe. Witnesses: 6" Maple, N70°W 19.01' - 12" Hemlock, EAST 26.45' - 5" Maple, S55°E 22.20' - 14" White Pine, S59°W 15.28'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.  
Found a DNR brass capped pipe at the south edge of a small lake. Also found all four bearing trees as shown on above mentioned Certificate of Survey.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Corner is a DNR brass capped pipe on the south edge of a small lake, approximately 330 feet north of the centerline of County Road 407. Witnesses:  
6" Maple, N70°W 19.01'  
12" Hemlock, EAST 26.45'  
5" Maple, S55°E 22.20'  
14" White Pine, S59°W 15.28'

Note: Distances are to a nail/tag #27450 in the side of the tree. Trees are blazed and painted.  
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96