

**SURVEY & REMONUMENTATION**

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
 Luce County Remonumentation Corner

For corners **SECTION**

Luce County	Located in:	Corner Code #
1. Public Land Survey	T46N R10W	F-3
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat ,		
5. Private Claims		

LUCE COUNTY  
 REGISTER OF DEEDS  
 Recorded  
*Liber 3 Page 793*  
 03-06-1998 10:45:49  
*Deborah Johnson, Dep.*  
 Kathy S. Mahar, Register  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3						●							
4								10		11		12	
5													
6	14		13		12		11		10		9		8
7													
8	17		16		15		14		13		12		11
9													
10													
11													
12													
13													

I, Keith R. Waters, in a field survey on September 23, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

F-3 1/4 Corner common to Sections 4 & 9, Town 46 North, Range 10 West

1853 - Original corner was established by George H. Cannon, D.S.  
 Witnesses: Beech 11, N43°E 21 links - Beech 11, S62°W 19 links

1957 - Michigan Department of Conservation, Forestry Division, Land Corner Record, Billy Buckler, RLS 8887  
 Recorded in Luce County Corner Records, page 169A. Found no evidence of original corner. Reestablished 1/4 corner midway on line between section corners. Witness: 6" Soft Maple, S22°E 153 links.

1996 - Certificate of Survey, William L. Karr, P.S. 27450. Found DNR brass capped pipe. Witnesses:  
 12" Ash, N24°W 76.69' - 14" Ash, N28°E 73.33' - 14" Ash, S27°E 42.91' - 24" White Pine, S19°W 69.93'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.  
 Found a 1" pipe with a brass DNR cap and all four bearing trees as called for in above mentioned 1996 Certificate of Survey (trees shown as ashes are actually cherries). Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" pipe with a brass DNR cap at the corner location, next to a rotted wood post.  
 Witnesses:

- 12" Cherry, N24°W 76.69'
- 14" Cherry, N28°E 73.33'
- 14" Cherry, S27°E 42.91'
- 24" White Pine, S19°W 69.93'

Note: Distances are to a nail/tag #27450 in the side of the tree.  
 Trees are blazed and painted.  
 Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142