

**SURVEY & REMONUMENTATION**

**APR 07 1998**

**LAND CORNER RECORDATION CERTIFICATE**

**Filing Requirement of Act 74, Mich. P.A. 1970**

Luce County Remonumentation Corner

For corners in **SECTION**

Luce County

Located in:

Corner Code #

- |                                    |   |           |               |
|------------------------------------|---|-----------|---------------|
| 1. Public Land Survey              |   | T46N R10W | G-2           |
|                                    |   | T R       |               |
|                                    |   | T R       |               |
|                                    |   | T R       |               |
| 2. Property Controlling in Section | S | T R       |               |
|                                    | S | T R       |               |
| 3. Miscellaneous Property in Sec.  | S | T R       |               |
|                                    | S | T R       |               |
| 4. Lot No.                         |   |           | Recorded Plat |
| 5. Private Claims                  |   |           |               |

LUCE COUNTY REGISTER OF DEEDS

Recorded  
Liber 3 Page 794  
03-06-1998 10:45:58

*Deborah Johnson, Dep.*  
Kathy S. Mahar, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6	15												
7													
8	19	9											
9													
10	30	19											
11													
12	31	30											
13													

I, Keith R. Waters, in a field survey on November 12, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-2 1/4 Corner common to Sections 3 & 4, Town 46 North, Range 10 West

1853 - Original corner was established by George H. Cannon, D.S.

Witnesses: Spruce 14, N81°E 16 links  
Cedar 12, S62°W 21 links

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.

Found a 2 1/4" diameter iron with a 1/2" hole in the center, 1 foot above ground. Found iron is 2893.2 feet from the section corner to the north, 2625 feet from the section corner to the south, and is 5.5 feet east of a straight line between said section corners. The north-south position is within 3 feet of a pro-rated GLO distance between the section corners north and south. Accepted corner as found.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 2 1/4" diameter iron with a 1/2" hole in the center, 1 foot above ground, at the corner location.

Witnesses:

- 10" Cedar, N46°E 22.64'
- 16" Cedar, N79°W 31.78'
- 6" Balsam Fir, S22°W 7.84'
- 5" Balsam Fir, S42°E 7.49'

Note: Distances are to a nail/tag #33142 in the side of the tree.  
Trees are blazed and painted.  
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142