

**SURVEY &  
REMONUMENTATION**

**APR 07 1998**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Luce County Remonumentation Corner

For corners in

Luce County	SECTION	Located in:	Corner Code #
1. Public Land Survey		T46N R10W	H-5
		T R	
		T R	
2. Property Controlling in Section	S	T R	
	S	T R	
3. Miscellaneous Property in Sec.	S	T R	
	S	T R	
4. Lot No.		Recorded Plat	
5. Private Claims			

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 3 Page 799*  
03-06-1998 10:46:51  
*Deborah Johnson, Dep.*  
Kathy S. Mohr, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6	18			10		15		14		13			
7													
8	19		20		21		22		23		24		
9													
10	30				8				26		21		
11													
12	31		32		33		34		35		36		
13													

I, Keith R. Waters, in a field survey on October 9, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-5 1/4 Corner common to Sections 10 & 15, Town 46 North, Range 10 West

1853 - Original corner was established by George H. Cannon, D.S.

Witnesses: Tamarack 11, N41°E 9 links  
Tamarack 10, S08°E 12 links

1980 - A sketch by Billy D. Buckler, RLS 8887, shows a computed distance of 5272.06 feet on the south side of Section 10, no mention is made of the 1/4 corner.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Luce County Remonumentation Program. Found no evidence of the corner or its accessories. Reestablished corner by single proportionate measurement midway on line between section corners east and west. The distance between said section corners is within 0.8 feet of that as shown on above mentioned DNR sketch by Buckler.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 1/2" x 48" rebar with a stamped aluminum Luce County Remonumentation cap at the corner location. Witnesses:

- 12" Cedar, N05°E 17.42'
- 10" Balsam Fir, S65°E 26.95'
- 12" Aspen, S60°W 23.58'
- 9" Spruce, N40°W 35.27'

Note: Distances are to a nail/tag #33142 in the side of the tree.  
Trees are blazed and painted.  
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142