

**SURVEY &  
REMONUMENTATION**

APR 07 1998

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970  
Luce County Remonumentation Corner

For corners in **SECTION**

Luce County	Located in:	Corner Code #
1. Public Land Survey	T46N R10W	I-5
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No.	Recorded Plat	
5. Private Claims		

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 3 Page 803*  
03-06-1998 10:47:26  
*Deborah Johnson, Dep.*  
Kathy S. Maher, Register  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Keith R. Waters, in a field survey on October 28, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

I-5 Corner common to Sections 10, 11, 14, & 15, T46N, R10W

1853 - Original corner was established by George H. Cannon, D.S.  
Witnesses: Tamarack 10, N10°E 12 links  
Cedar 10, S30°W 30 links

1963 - Michigan Department of Conservation, Forestry Division, Land Corner Record, Billy D. Buckler, RLS 8887.  
Recorded in Luce County Corner Records, page 458A. Corner was reestablished on an old line of north-south blazes and from an old stream bed 3.16 chains south. Another old stream bed 10.20 chains south fits record.  
Witnesses: 10" Cedar Stub, N28°E 19 links - 12" Cedar Stub, N54°W 17 links.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.  
Found a 1" iron pipe with an aluminum DNR cap and the remains of the cedar stub witness northwest as called for in the 1963 DNR records. Accepted corner as found and established new bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" iron pipe with an aluminum DNR cap at the corner location, which falls approximately 330 feet northeasterly of the center of an old railroad grade.  
Witnesses:

- 5" White Birch, N79°W 19.11'
- 5" White Birch, S62°E 48.22'
- 8" Balsam Fir, S46°E 61.52'
- 5" Spruce, S24°E 42.96'

Note: Distances are to a nail/tag #33142 in the side of the tree.  
Trees are blazed and painted.  
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142