

**SURVEY &
REMONUMENTATION**

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Luce County Remonumentation Corner

LUCE COUNTY
REGISTER OF DEEDS

Recorded
Liber 3 Page 805
03-06-1998 10:47:46

Deborah Johnson, Dep.
Kathy S. Malar, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Luce County **SECTION**

Located in:

Corner Code #

- | | | | |
|------------------------------------|---|---------------|-----|
| 1. Public Land Survey | | T46N R10W | J-5 |
| | | T R | |
| | | T R | |
| | | T R | |
| 2. Property Controlling in Section | S | T R | |
| | S | T R | |
| 3. Miscellaneous Property in Sec. | S | T R | |
| | S | T R | |
| 4. Lot No. | | Recorded Plat | |
| 5. Private Claims | | | |

I, Keith R. Waters, in a field survey on October 29, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-5 1/4 Corner common to Sections 11 & 14, Town 46 North, Range 10 West

1853 - Original corner was established by George H. Cannon, D.S.

Witnesses: Cedar 18, S20°E 17 links
Cedar 12, N40°W 19 links

1963 - Michigan Department of Conservation, Forestry Division, Land Corner Record, Billy D. Buckler, RLS 8887
Recorded in Luce County Corner Records, page 457A. Corner replaced from two original cedar bearing trees, a stump bearing S20°E 17 links and a down cedar bearing N40°W 19 links. Set 1" pipe with aluminum cap.
Witnesses: 7" White Birch, S10°W 24 links - 7" Aspen, S70°E 21 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being perpetuated as part of the Luce County Remonumentation Program.
Found a 1" iron pipe with an aluminum DNR cap and both bearing trees as called for in 1963 DNR records.
Accepted corner as found and established additional bearing trees.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found a 1" iron pipe with an aluminum DNR cap the corner location.
Witnesses:

- 10" White Birch, S18°W 15.83'
- 10" Aspen, S65°E 14.39'
- 6" Balsam Fir, N30°E 46.52'
- 8" White Birch, N46°W 32.61'

Note: Distances are to a nail/tag #33142 in the side of tree.
Trees are blazed and painted.
Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

