

**SURVEY &
REMONUMENTATION**

APR 07 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
Luce County Remonumentation Corner

For corners **SECTION**

Luce County	Located in:	Corner Code #
1. Public Land Survey	T46N R10W	K-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

LUCE COUNTY
REGISTER OF DEEDS
Recorded

Liber 3 Page 808
03-06-1998 10:48:23

Deborah Johnson, Dep.
Kathy S. Major, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on December 22, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-4 1/4 Corner common to Sections 11 & 12, Town 46 North, Range 10 West

1853 - Original corner was established by George H. Cannon, D.S.
Witnesses: Spruce 14, N15°W 13 links
Hemlock 16, S18°W 28 links

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being reestablished as part of the Luce County Remonumentation Program.
Found no evidence of this corner or its accessories. Reestablished corner by single proportionate measurement midway on line between section corners K-3 to the north and K-5 to the south.
(Note: The position used for the section corner K-3 is not the previously recorded position as shown in LCRC's in liber 2, pages 641, 680, and 683).

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Placed a 1/2" rebar with a plastic cap #33142 at the corner location, which falls 7 feet west of the centerline of Highway M123 and 4.5 feet south of the centerline of County Road 446 to the west.
Witnesses:

Power Pole (ML1-105), S70°W 68.94'
Power Pole, N32°W 126.60'
10" Spruce, N88°E 85.24'
Power Pole, N16°E 278.32'

Note: Distances are to a nail/tag #33142 in the side of the witness object.
Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters

Date 12-30-97

Surveyor's Michigan License No. 33142

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				
3													
4			3		2		1						
5													
6	18		17		16		15		14		13		12
7													
8	19		20		21		22		23		24		25
9													
10	30		29		28		27		26		25		24
11													
12													
13													
14													
15													

