

LUCE COUNTY REMONUMENTATION CORNER

1993  
REMONUMENTATION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

For corners in  
Luce

|                                       |                         |               |
|---------------------------------------|-------------------------|---------------|
| _____ (County)                        | Located In:             | Corner Code # |
| 1. Public Land Survey                 | T 46N R 10W             | L-9           |
|                                       | T _____ R _____         | _____         |
|                                       | T _____ R _____         | _____         |
| 2. Property Controlling in Section    | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 3. Miscellaneous Property in Sec.     | S _____ T _____ R _____ | _____         |
|                                       | S _____ T _____ R _____ | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                         |               |
| 5. Private Claims _____               |                         |               |

Filed 12-22 A.D., 1993

At 10:00 o'clock A.M.

File No. 99 502

*Keith R. Waters*  
Luce County Reg. of Deeds

Register of Deeds Stamp & File Number

I, Keith R. Waters, in a field survey on December, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

L-9 1/4 Corner Common to Sections 24 & 25, T46N, R10W

Original ties to post:  
Cedar 8, N50°W 21 links  
Cedar 10, S59°E 22 links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

L-9

This corner is being re-established as part of the Luce County Remonumentation Program. Found no evidence of corner. Re-established corner 33 feet south and 33 feet east of a fence corner at the northwest corner of County Road 462 east-west and County Road 430 north-south. Right-of-way fences on County Road 430 to the north run very straight and are 66 feet apart. Using this position for 1/4 corner, distance from section line north to a galvanized pipe with aluminum cap at the northeast corner of County Roads 462 and 430 is 33.00 feet. Distance from section line to a galvanized pipe with aluminum cap on the north side of County Road 462, approximately 1/4 mile east of County Road 430, is also 33.00 feet. Distance to section corner east is 2618.80 feet and distance to section corner west is 2603.22 feet. Corner is 4.65 south of a straight line between said section corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-9

Corner is a 1/2" rebar with 3 1/4" aluminum Luce County cap 4 feet north of centerline of County Road 462, at centerline of County Road 430. Witnesses:

- Corner Fence Post, N45°W 46.87'
- Power Pole, N35°E 43.89'
- Power Pole (6-14), S26°E 48.67'
- Galvanized Pipe w/aluminum cap at Base of Wood Post, N42°E 42.68'

Note: Distances to fence post and power poles are to a nail and tag in the side. Bearings are compass bearings corrected for declination.

| A  | B  | C  | D  | E  | F  | G  | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |



Signed by Keith R. Waters

Date 12-20-93

Surveyor's Michigan License No. 33142