

MAY 28 1997

COMMISSION

**LUCE COUNTY REMONUMENTATION CORNER**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce _____ (County)	Located In:	Corner Code #
1. Public Land Survey	T46N R 9W	A-1 Same
	T46N R 10W	M-1 Corner
	T47N R 9W	A-13 (Township
	T47N R 10W	M-13 Corner)
2. Property Controlling in Section	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

LUCE COUNTY  
REGISTER OF DEEDS  
Recorded  
*Liber 2 Page 715*  
02-28-1997 08:55:13  
*Kathy S. Mahan*  
Kathy S. Mahan, Register  
REGISTER OF DEEDS

**Register of Deeds Stamp & File Number**

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Keith R. Waters, in a field survey on 03/06, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

**A. Description of original monument and accessories and/or subsequent restoration:**


A-1 (M-1) (A-13) (M-13) Township Corner Common to Townships 46 & 47 North, & Ranges 9 & 10 West  
1841 - Original ties to set post (John Burt): Tamarack 10, N50°E 36 links - Tamarack 10, S73°W 15 links.  
1958 - Harold R. Bruning, District Forester, Escanaba Paper Company, page 363A of Luce County Recorded corners.  
Re-established corner from standing dead original tamarack bearing tree and original tamarack bearing tree stump.  
Placed a 4 foot x 1 1/4" diameter galvanized iron pipe with a stamped Escanaba Paper Company cap. A 4 inch squared and scribed cedar post was set next to the iron pipe. Witnesses: 4" cedar, N44°W 62 1/2 links - 5" Cedar, S66°W 34 links - 4" cedar, S50°E 11 1/2 links - 4" cedar, N48°E 50 1/2 links.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

This corner is being perpetuated as part of the Luce County Remonumentation Program.  
Found an iron pipe with a stamped Escanaba Paper Company cap next to a squared, scribed post and all four bearing trees as described above.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Corner is an iron pipe with a stamped Escanaba Paper Company cap next to a squared, scribed post.  
Witnesses:  
7" Cedar, N46°W 41.29' (existing bearing tree)  
8" Cedar, S50°E 7.46' (existing bearing tree)  
9" Cedar, S63°W 22.31' (existing bearing tree)  
6" Cedar, N54°E 33.60' (existing bearing tree)  
8" Cedar, S23°W 15.87'  
Note: Distances are to a nail/tag P.S. 33142 in the side of the witness object. Trees are blazed and painted.  
Bearings are compass bearings corrected for declination.



Signed by Keith R. Waters  
Surveyor's Michigan License No. 33142

Date 12-30-96