

MAY 28 1997

COMMISSION

LUCE COUNTY REMONUMENTATION CORNER

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LUCE COUNTY
REGISTER OF DEEDS

Recorded
Liber 2 Page 722

02-28-1997 08:56:31

Kathy S. Mahan
Kathy S. Mahan, Register
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

Luce
(County)

Located In:

Corner Code #

1. Public Land Survey

T46N R 9W A-7/8 Same
T46N R 10W M-7/8 Corner

2. Property Controlling
in Section

S T R

3. Miscellaneous
Property in Sec.

S T R

#2

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

I, Keith R. Waters, in a field survey on 11/08, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													


A. Description of original monument and accessories and/or subsequent restoration:

A-7/8 (M-7/8) Witness Corner to Meander Corner Between Section 19, T46N, R9W & Section 24, T46N, R10W, S. Side River
1841 - The original meander corner (John Burt) was a 4" cedar. Witness: Hemlock 12, N80°W 10 links.
Original notes indicate that the meander corner was 3.31 chains south of the section corner position, which falls in the Tahquamenon River.

Found no evidence of subsequent restoration of this corner.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

This corner is being re-established as part of the Luce County Remonumentation Program.
Found no evidence of corner. Re-established corner on line between recovered 1/4 corners north and south, on the south bank of the Tahquamenon River. Corner falls 265.84 feet south of the pro-rated section corner position and 45.02 feet south of the pro-rated meander corner position.



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Corner is a 1/2" rebar with a stamped aluminum Luce County Remonumentation cap on the south bank of the Tahquamenon River. Witnesses:
7" Cedar, N48°E 11.14'
8" White Birch, S56°E 2.54'
6" Hemlock, N23°W 15.96'
12" White Birch, S71°W 9.96'



Note: Distances are to a nail/tag P.S. 33142 in the side of the witness object. Trees are blazed and painted. Bearings are compass bearings corrected for declination.

Signed by Keith R. Waters
Surveyor's Michigan License No. 33142

Date 12-30-96