

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Luce	Located In:	Corner Code #	
<small>(County)</small>			
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>3</u> T <u>46N</u> R <u>10W</u>	<u>1</u>	
	S ___ T ___ R ___	_____	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Jun 19 2000

I, Stephan J. Szyszkoski, in a field survey on _____, 19____ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4				3		2		1	
3												
4	7	8	9				10		11		12	
5												
6	18	17	16				15		14		13	
7												
8	19	20	21				22		23		24	
9												
10	30	29	28				27		26		25	
11												
12	31	32	33				34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (1-Sec. 3) West 1/16 corner between Sec. 3 T46N-R10W and Sec. 34, T47N-R10W. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(1-Sec. 3) Established the corner midway and on a line of mean true bearing between Section corner 1318.56' West and Quarter corner 1318.56' East. Placed a 1" ID x 36" iron pipe capped with a 4" dia. MDNR tablet at the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(1) Set 1" pipe with 4" MDNR cap.


Blazed, scribed, and set measuring nails

in the following:

- 10" Cedar N43W 7.6' "W1/16 BT"
- 8" Cedar N22E 2.6' do
- 10" W. Birch N83E 21.95' do
- 6" Cedar S52W 6.4' do

Center of road, North 76.5'

Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 8/29/00

For the Michigan Department of Natural Resources - Forest Management Division