

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce
 (County)

Located In: _____ Corner Code F2

- | | | | | | | | |
|------------------------------------|---|------------|---|------------|-----------|------------|----------|
| 1. Public Land Survey | T | <u>46N</u> | R | <u>10W</u> | <u>F2</u> | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| | T | _____ | R | _____ | _____ | | |
| 2. Property Controlling in Section | S | <u>4</u> | T | <u>46N</u> | R | <u>10W</u> | <u>4</u> |
| | S | _____ | T | _____ | R | _____ | _____ |
| 3. Miscellaneous Property in Sec. | S | _____ | T | _____ | R | _____ | _____ |
| | S | _____ | T | _____ | R | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

4 Dec 02 1999
 F2 Feb 25 1999

I, Stephan J. Szyszkoski, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5				3		2		1		
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:


(F2) Center of Section 4. Corner not established in the original survey. Found no subsequent record.
 (4-Sec. 4) Northwest 1/16 corner of Section 4. Corner not established in the original survey. Approximate corner established by MI Dept. of Conservation foresters ca. 1957-1960 who set wooden post at "approximate forty corner". Eino Sainio, PS placed "t"-iron at location of this post in 1984 (survey recorded L2-P28, Luce County Records).

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F2) Found no evidence of prior monumentation at the corner position. Established the corner at the intersection of straight lines connecting opposite 1/4 corners. At the position for the corner I placed a 1"ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. I used the 1/4 corner between Sections 4-5 as recorded by Keith Waters, PS, and approved by the Luce Co. Remonumentation Peer Review 12/12/97, to control the E-W 1/4 line in the establishment of this corner.
 (4-Sec. 4) Recovered the "t"-iron placed by Mr. Sainio and the remains of the approximate post. Established the corner at the intersection of straight lines connecting opposite 1/16 corners. The "t"-iron is N05W (magnetic), 7.3' from this position. At the position for the corner, I placed a 1"IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F2) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 14" R. Pine N80W 27.35' "CS BT" 6" R. Pine S72W 27.25' do 5" W. Birch S17E 13.6' do 6" W. Birch in clump N56E 15.6' "CS BT" Placed 3" cedar post adjacent. Bearings are magnetic	(4) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 24" Maple N54W 30.2' "NW1/16 BT" 18" Maple N24E 26.5' do 4" Cherry East 2.7' do 6" W. Birch S43E 21.1' do T-iron N5W 7.3' Placed squared cedar post adjacent. Bearings are magnetic.
--	--



Signed by Stephan J. Szyszkoski Date 2/22/00
 Surveyor's Michigan License No. 33986