

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in  
Luce

(County)	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>4</u> T <u>46N</u> R <u>10W</u>	<u>5</u>
	S <u>4</u> T <u>46N</u> R <u>10W</u>	<u>7</u>
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

7 Feb 25 1999  
 5 Dec 02 1999

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_\_, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

(5-Sec. 4) North 1/16 corner of Section 4. Corner not established in the original survey. Approximate corner established by MI Dept. of Conservation foresters ca. 1957-1960 who set wooden post at "approximate forty corner". Eino Sainio, PS placed "t"-iron at the location of this post in 1984 (survey recorded in L.2-P.28 Luce County Records).  
 (7-Sec.4) North 1/16 corner between Sections 3-4. Corner not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

(5-Sec. 4) Recovered the "t"-iron placed by Mr. Sainio and the remains of the approximate post. Established the corner 20 chains proportionate measure north of the center of Section 4. Proportion based on mean of original measure on E and W sides of Section 4. At the position for the corner, I placed a 1" ID x 36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the monument, I measure 1532.00' north and 1314.17' south to adjacent 1/4 corners. The "t"-iron is N03W(magnetic), 7.82' from the established corner.  
 (7-Sec. 4) Found no evidence of prior monumentation at the corner position. Established the corner 20 chains, proportionate to the original record, north of the quarter corner between Sections 3-4 and on a straight line between the quarter corner and the Northeast corner of Section 4. At the position for the corner, I placed a 1" IDx36" iron pipe capped with a 4" dia. cast aluminum MDNR tablet, appropriately stamped. From the monument, I measure north 1583.36' and south 1309.65' to adjacent corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(5) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 24" Maple S40W 14.95'      "N1/16 BT" 8" Y. Birch N35W 28.35'      do 6" Maple N22E 23.75'      do 5" Beech S33E 27.95'      do 1 iron N3W 7.82' Placed squared cedar post adjacent. Bearings are magnetic.	(7) Set 1" pipe with 4" MDNR cap. Blazed, scribed, and set measuring nails in the following: 6" Cedar N03W 32.9'      "N1/16 BT" 4" Cedar N51W 20.55'      do 6" Cedar S01W 15.5'      do 8" W. Birch S32W 18.25'      do Placed 4" cedar post adjacent. Bearings are magnetic.
--	---



Signed by Stephan J. Szyszkoski Date 2/22/00  
 Surveyor's Michigan License No. 33986