

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Luce

	Located In:	Corner Code #
(County)		
1. Public Land Survey	T <u>46N</u> R <u>10W</u>	<u>H4</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u>10</u> T <u>46N</u> R <u>10W</u>	<u>12</u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

Apr 01 2003

I, Stephan J. Szyszkoski, in a field survey on _____, 20__ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4				3		2		1	
3												
4	7	8	9				●		11		12	
5							●					
6	18	17	16				15		14		13	
7												
8	19	20	21				22		23		24	
9												
10	30	29	28				27		26		25	
11												
12	31	32	33				34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:
 (H4) Center of Section 10. Not established in the original survey.
 (12-Sec. 10) South 1/16 corner, Section 10. Not established in the original survey.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
 (H4) Found a 1/2" dia. iron bar with plastic cap 27450 placed by William L. Karr PS at the intersection of straight lines connecting opposite 1/4 corners. Accepted same as a careful and faithful determination of the position of the corner.
 (12-Sec. 10) Found a 1/2" iron bar with plastic cap 27450 placed by William L. Karr PS midway and on a straight line between Quarter corner to south and Center of Section to north. Accepted same as a careful and faithful determination of the position of the corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
 (H4) Found 1/2" iron bar with plastic cap #27450. Blazed, scribed, and set measuring nails in:
 8" Spruce N16E 3.45' CS BT
 6" Balsam S21E 21.15' do
 13" triple Maple S75W 26.35' do
 12" W. Birch N04W 14.9' do
 Bearings are magnetic. Distances are to nail with tag.
 (12) Found 1/2" dia. iron bar with plastic cap #27450. Blazed, scribed, and set measuring nails in:
 16" Spruce S19E 49.5' S1/16 BT
 10" Balsam N70W 21.5' do
 4" Balsam N48E 5.3' do
 7" Cedar S63E 28.25' do
 Bearings are magnetic. Distances are nail with tag.



Signed by Stephan J. Szyszkoski
 Surveyor's Michigan License No. 33986

Date 4/7/03