

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce

(County)

Located In:

Corner Code #

- |                                    |      |             |   |
|------------------------------------|------|-------------|---|
| 1. Public Land Survey              | T    | R           |   |
|                                    | T    | R           |   |
|                                    | T    | R           |   |
|                                    | T    | R           |   |
| 2. Property Controlling in Section | S 13 | T 46N R 10W | 1 |
|                                    | S 13 | T 46N R 10W | 8 |
| 3. Miscellaneous Property in Sec.  | S    | T           | R |
|                                    | S    | T           | R |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

Jan 08 2003

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

- A. Description of original monument and accessories and/or subsequent restoration:**  
 (1-Sec. 13) West 1/16 corner between Sections 12-13. Not established in the original survey. Found no subsequent record.  
 (8-Sec. 13) West 1/16 corner, Section 13. Not established in the original survey. Found no subsequent record.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 (1-Sec. 13) Established the corner midway and on a line of mean true bearing between Section corner 1307.18' west and Quarter corner 1307.18' east.  
 (8-Sec. 13) Established the corner midway and on a straight line between Quarter corner 1309.11' west and Center of Section (unmonumented) 1309.11' east.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**
- |   |   |
|---|---|
| (1) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:<br>5" Balsam N21W 21.3' "N1/16 BT"<br>4" Balsam S42W 24.9' do<br>20" Tamarack S62E 28.15' do<br>4" twin Balsam N85E 26.0' do<br>Bearings are magnetic. Distances are to nail with tag. | (8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in:<br>6" Spruce S81W 22.5' "N1/16 BT"<br>8" Spruce S02W 16.8' do<br>5" Spruce S55E 24.65' do<br>10" Spruce N61E 18.05' do<br>Bearings are magnetic. Distances are to nail with tag. |
|---|---|



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/29/03