

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #	
1. Public Land Survey	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
	T ___ R ___	_____	
2. Property Controlling in Section	S <u>1</u> T <u>46N</u> R <u>10W</u>	<u>15</u>	
	S <u>10</u> T <u>46N</u> R <u>10W</u>	<u>4</u>	
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	
	S ___ T ___ R ___	_____	

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

4 Dec 03 2002  
 15 Nov 02 2002

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

**A. Description of original monument and accessories and/or subsequent restoration:**  
 (15-Sec. 1) West 1/16 corner between Sections 1 and 12. Not established in the original survey. Found no subsequent record.  
 (4-Sec. 10) Northwest 1/16 corner, Section 10. Not established in the original survey. Found no subsequent record.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**  
 (15-Sec. 1) Established the corner midway and on a line of mean true bearing between Section corner 1312.07' West and Quarter corner 1312.07' East.  
 (4-Sec. 10) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

(15) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 14" Balsam N70W 18.2' "W1/16 BT" 12" Balsam N88W 36.55' do 6" W.Birch N72E 20.85' do 10" Cherry S80E 19.15' do Bearings are magnetic. Distances are to nail with tag. An angle iron fence post is adjacent.	(4) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 12" R.Maple S19E 21.0' "NW1/16 BT" 10" Cedar West 18.7' do 8" Cedar N61W 24.4' do 9" Spruce N76E 25.3' do Bearings are magnetic. Distances are to nail with tag. A N-S barbed wire fence is 22' east of the monument.
--	---



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/29/03