

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Luce

(County)

Located In:

Corner Code #

1. Public Land Survey	T <u>46N</u> R <u>10W</u>	<u>J2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>2</u> T <u>46N</u> R <u>10W</u>	<u>8</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

J2 Jan 08 2003  
 8 Dec 09 2002

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		●	●		1
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 20\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
 (J2) Center of Section 2. Not established in the original survey. Found no subsequent record.  
 (8-Sec. 2) West 1/16 corner, Section 2. Not established in the original survey. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
 (J2) Established the corner at the intersection of straight lines connecting opposite quarter corners. The corner falls in the southerly shoulder of a county road.  
 (8-Sec. 2) Established the corner midway and on a straight line between Quarter corner 1319.94' West and Center of Section 1319.94' East.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(J2) Set 5/8"x24" iron reinforcing rod with plastic cap stamped "Mich DNR PS 33986". Set measuring nails in: Power pole N15W 54.15' Fence post S43W 14.75' Fence post S47E 16.1' Fd. a 3/4" ID iron pipe N6W 53.0' Centerline of road is North 17.6' A fence runs south from the corner. Bearings are magnetic.	(8) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Blazed, scribed, and set measuring nails in: 5" Maple S14E 13.15' "W1/16 BT" 8" Maple N45W 5.95' do 10" Maple S85W 19.0' do 12" Beech S16W 36.75' do Bearings are magnetic. Distances are to nail with tag. Placed cedar post adjacent.
--	--



Signed by Stephan J. Szyszkoski  
 Surveyor's Michigan License No. 33986

Date 1/29/03