

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 46 NR. 11 W

--- L u e e --- COUNTY

DESCRIPTION OF CORNER Section corner common to Section 2, 3, 10, and 11.

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 13" Beech (S 3 NBT) N 21° W 38 1/2 Links

12" Hemlock (S 2 NBT) N 44° E 52 1/2 Links

10" Hemlock (S 11 NBT) S 12° E 40 1/2 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced as set by J. McLaren, Newberry. Found wood post and probable Beech B.T. bearing N 40° W 13 Links. Tree green and standing, has been chopped out. No scribe marks. Found Yellow Birch line tree 10.63 chains south of corner. This tree has been out and is laying on the ground, ~~which~~ we could not determine what stump the log came from.

Corner was placed and witnessed May 3, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 5/18/60