

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T~~46~~ 47 NR. 11 W.

----- L u s e ----- COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 4, 5, 32, 33

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass Cap

WITNESSES TO CORNER 9" W. Pine (S 5 NBT) S 55° W 170 1/2 Links

9" Aspen (S 33 NBT) N 49° E 78 Links

1" Iron Pipe West 41 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was re-established by single proportionate measure along township line, from corners 1 mile west and 1 mile east.

Corner was placed and witnessed May 12, 1960 with Frank J. Bray.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR
Billy D. Buckler

DATE 5/23/60